

SURVEY &  
REMONUMENTATION

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

JAN 17 1996

2213

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 296

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

PRESQUE ISLE COUNTY  
REGISTER OF DEEDS  
95 OCT 20 PM 4:28  
*Janet M. Lamb*  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, Norman J. Quaine in a field survey on June 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1  
GLO Notes  
Resurvey 1856  
Black Ash 9" N25°W 26  
Cedar 11" N45°E 38  
George H. Cannon

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1  
June 7, 1995  
Presque Isle County  
State Remonumentation  
Norman J. Quaine #33984  
Porter's Survey P.C.

Fd. no evidence of corner's position  
Set 1/2" Rod & Cap #33984  
By single proportion

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1  
Left 1/2" Rod & Cap #33984  
N39°E 9.18' 9" Maple in clump  
S16°E 12.65' 9" Maple in clump  
S53°W 14.84' 5" Ash  
N53°W 14.97' 6" Ash

Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *Delmer E. Porter*  
Date 9/20/95

\*Witness tags & nails used.

Signed by Norman J. Quaine Date OCTOBER 19, 1995  
Surveyor's Michigan License No. 33984