

1995 JAN 17 1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

2030 COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|---------------------------|----------------|
| <u>PRESQUE ISLE</u> (County) | Located In: | Corner Code #/ |
| 1. Public Land Survey | T <u>36</u> N R <u>2E</u> | <u>J-3</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

LIBER **316** PAGE **313**
 PRESQUE ISLE COUNTY
 REC'D
 95 OCT 20 PM 4: 34
Jane M. Smith
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Ronald Bischer, in a field survey on March 3, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | |
|-------------------------------|-------------------------------------|
| GL0 Notes - 1856 Resurvey | S72°W 33.45' 10" Norway |
| Geo. H. Cannon | S25°E 14.98' 5" Cedar |
| Set wood post | |
| Spruce pine 11" N50°W 36½ lks | 02-05-93 - Ronald R. Bischer |
| W. pine 10" S70°W 77 lks | ½" Rod and Cap #15410 |
| | witnesses same as Porter - 02-02-78 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" Rod and Cap #15410 at fence corner
 S70°W 33.45' 13" Norway
 S18°E 15.01' 7" Cedar
 N13°W 8.71' 11" Spruce - earlier recorded as W. Pine



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

½" Rod and Cap #15410
 S70°W 33.45' 13" Norway Pine
 S18°E 15.01' 7" Cedar
 N13°W 8.71' 11" Spruce
 N42°E 22.85' 7" Cedar

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Delmar E. Porter*
 Date 9/20/95

Nails with witness tag #22428 used.

Signed by Ronald R. Bischer Date Oct. 3, 1995
 Surveyor's Michigan License No. 22428