

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

2031

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **316** PAGE **314**
PRESQUE ISLE COUNTY
RECORDED

For corners in <u>PRESQUE ISLE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>J-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

95 OCT 20 PM 4:31

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5									●			
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Ronald Bischer, in a field survey on July 27, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Resurvey - GLO Notes
Geo. H. Cannon
Set Wood Post
Tamarack 10" N66°W 20 lks
Spruce 9" S43°E 30 lks

2-2-88 Delmar E. Porter #15410
Set 1/2" Rod and Cap by Single Proportion
N65°E 54.21' 12" W. Pine S50°E 69.21' 4" Balsam
N76°W 51.00' 4" Balsam

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rod and Cap #15410
N65°E 54.21' 12" W. Spruce
N76°W 51.00' 4" Spruce
S50°E 69.21' 5" Balsam



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" Rod and Cap #15140
N65°E 54.21' 12" W. Spruce
N76°W 51.00' 4" Spruce
S50°E 69.21' 5" Balsam
N57°W 67.90' 16" Aspen

Nails with witness tag #22428 used.

Ratified by Peer Group
in accordance with P.A. 345
Chairman *John E. Pata*
Date 9/26/95

Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date Oct 3, 1995