

0350

**JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE**

95 OCT 20 PH 4: 31

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
PRESQUE ISLE  
 (County)

**COMMISSION**  
 Located In:

Corner Code #

*Janet M. Lamb*  
 REGISTER OF DEEDS

- |                                      |   |            |   |           |            |
|--------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey                | T | <u>36N</u> | R | <u>2E</u> | <u>K-2</u> |
|                                      | T | _____      | R | _____     | _____      |
|                                      | T | _____      | R | _____     | _____      |
|                                      | T | _____      | R | _____     | _____      |
| 2. Property Controlling in Section   | S | _____      | T | _____     | _____      |
|                                      | S | _____      | T | _____     | _____      |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | _____      |
|                                      | S | _____      | T | _____     | _____      |

LIBER **316** PAGE **303**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Ronald Bischer, in a field survey on July 26, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1856 Resurvey - GLO Notes                      N65°E 13.66' 14" Cedar  
 Geo. H. Cannon                                    N75°E 14.85' OBT Stump  
 Set Wood Post                                    S80°E 33.76' 6" Cedar  
 Tamarack 10" N75°E 22½ lks  
 Cedar 6" S22½°W 12 lks  
 1-17-76, 7-27-76, 4-29-77, 4-18-84.  
 Delmar E. Porter, 1" Pipe, same witnesses as  
 in 12-1-75.  
 12-1-75 Delmar E. Porter  
 #15410 - Fd. 1" Pipe & 3"x3"  
 Cedar post                                        2-24-94 Ronald R. Bischer #22428  
 S22°W 7.92' OBT                                1" Pipe - Same wit. as Porter - 12-1-75

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" Pipe, set ½" Rod and Cap #22428 inside of pipe.  
 S83°E 33.76' 12" Cedar  
 N65°E 13.66' 16" Cedar  
 S52°E 35.67' 10" Cedar



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

½" Rod and Cap #22428 in 1" Pipe  
 S83°E 33.76' 12" Cedar  
 N65°E 13.66' 16" Cedar  
 S52°E 35.67' 10" Cedar  
 N07°W 25.46' 6" Cedar

**Ratified by Peer Group**  
 in accordance with P.A. 345  
 Chairman *Delmar E. Porter*  
 Date 9/20/95

Nails with witness tag #22428 used.

Signed by Ronald R. Bischer  
 Surveyor's Michigan License No. 22428

Date Oct. 3, 1995