

2223

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 306

For corners in PRESQUE ISLE (County) Located in: _____ Corner Code # _____

1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

PRESQUE ISLE COUNTY
RECORDED

95 OCT 20 PM 4: 31

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Ronald Bischer, in a field survey on July 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Resurvey - GLO Notes	S29 W 32.96' 7" Cedar
Geo. H. Cannon	11-19-87 Delmar E. Porter #15140
Set Wood Post	3" Pipe, wit. same as 8-19-76 (Bischer).
Tamarack 12" N60°W 10 lks	1-10-95 Norman J. Quaine #33984
Aspen 14" N79°E 16 lks	Found 1" Pipe 18" below road surface,
8-19-76 Ronald R. Bischer #22428	raised with 1/2" Rod & Cap #33984
Found 1" Pipe set by Doyle	N61°E 52.04' SW Cor. Stone House
N66°W 39.52' 4" Balsam	S51°E 36.22' 10" Cedar
N64°E 52.09' Stone House	S57°W 61.87' 12" Spruce S86°W 48.00'
	7" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rod and Cap #33984
 N61°E 52.04' SW Cor. Stone House
 S51°E 36.22' 10" Cedar
 S57°W 61.87' 12" Spruce
 S86°W 48.00' 7" Cedar



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" Rod and Cap #33984
 N61°E 52.04' SW Cor. Stone House
 S51°E 36.22' 10" Cedar
 S57°W 61.87' 12" Spruce
 S86°W 48.00' 7" Cedar

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmar E. Porter*
Date 9/20/95

Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date Oct. 3, 1995