

SURVEY &
 1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION

LIBER **316** PAGE **316**

For corners in
PRESQUE ISLE
 (County)

Located In:

Corner Code #

PRESQUE ISLE COUNTY
 RECORDED

95 OCT 20 PM 4:34

Jenit M. Lamb
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- | | | |
|--------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>36N</u> R <u>2E</u> | <u>K-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald Bischer, in a field survey on August 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes - 1856 Resurvey Geo. H. Cannon Set wood post Cedar 12" N50½°E 9 lks Cedar 12" S61°W 17 lks 08-19-76 - Ronald R. Bischer Found ½" Pipe N59°W 122.78' 7" W. Pine	N45°E 63.01' 4" W. Pine S17°E 102.06' Power pole 09-14-78 - Delmar E. Porter, #15410 ½" Pipe, set monument box used three witnesses by Bischer, 08-19-76
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" pipe in monument box, replaced ½" pipe with ½" Rod and Cap #22428.
 S17°E 102.06' Power pole
 N59°W 122.78' 12" W. Pine
 N45°E 63.01' 10" W. Pine



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

½" Rod and Cap #22428 in monument box
 S17°E 102.06' Power pole
 N59°W 122.78' 12" White Pine
 N45°E 63.01' 10" White Pine
 S28°W 77.92' 15" White Pine

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *[Signature]*
 Date 9/20/95

Nails with witness tag #22428 used.

Signed by Ronald R. Bischer
 Surveyor's Michigan License No. 22428

Date Oct. 3, 1995