

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

94 AUG 23 AM 10:11

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>PRESQUE ISLE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Jane M. Lamb
REGISTER OF DEEDS

LIBER **310** PAGE **937**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald Bischer, in a field survey on April 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13
GLO Notes, Resurvey 1856
Set Wood Post
Sp. Pine 10" S20°E 16 links
Sp. Pine 7" S32°W 12 links
1935 - Marcus Schaaf
Set 2" Pipe
1979 - Ronald R. Bischer
Found 2" pipe

N24°W 49.59' 9" Balsam
N70°E 32.12' 16" Maple
N76°W 47.37' 18" Maple
1979 - Delmar E. Porter
Replaced pipe w/Concrete Monument w/brass cap
N24°W 49.48' 9" Balsam
N70°E 32.13' 16" Maple
S76°W 47.35' 18" Maple


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13
Found Concrete Monument with brass cap lettered "Presque Isle County Remonumentation Monument"
N28 W 49.59' 9" Balsam found foot blaze
N70 E 32.12' 20" Maple found foot blaze
S76 W 47.37' 18" Maple found foot blaze

SURVEY &
REMONUMENTATION

SEP 09 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13
Presque Isle County Remonumentation Monument
N28°W 49.59' 9" Balsam
N70°E 32.12' 20" Maple
S76°W 47.37' 18" Maple
S30°E 37.55' 4" Maple

Ratified by Peer Group
in accordance with P.A. 345

Chairman Delmar E. Porter
Date July 27, 1994

*Witness tags w/nails used.

Signed by Ronald R. Bischer Date July 20, 1994
Surveyor's Michigan License No. 22428