

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 297

PRESQUE ISLE COUNTY
REGISTER

95 OCT 20 PM 4: 29

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Presque Isle
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 36N R 2E L-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Norman J. Quaine in a field survey on February 17, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-1
 GLO Notes Made reference to in Dec 1975
 Resurvey 1856 the Plat of "Bella Vista" Delmer E. Porter #15410
 Tamarack 6" N50°E 24 of T37N,R2E, Sec. 36, Dated LCRC Page 98
 Tamarack 9" N20°W 10 8/24/72, by R.S. Scott Fd 1" Axle w/ old 3"x3" Cedar
 George H. Cannon As recorded in Presque Isle stake & newer 3"x3" cedar stl
 Co. Register of Deeds Left Same
 North 9.41' 7" Cedar
 S50°W 11.04' 6" Cedar
 S88°W 4.24' 6" Balsam

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1
 February 17, 1995 Fd. 1" Axle by cedar post
 Presque Isle County S88°W 4.24' 6" Balsam Stump
 State Remonumentation S50°W 11.04' 6" Cedar in poor condition
 Norman J. Quaine #33984 N23°E 9.25' 7" Cedar
 Porter's Survey P.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1
 Left 1" Axle by cedar post
 N23°E 9.25' 7" Cedar
 S71°E 10.48' 6" Cedar
 S12°W 12.20' 9" cedar
 N16°W 16.54' 5" Cedar

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Delmer E. Porter*
 Date 9/20/95

*Witness tags & nails used.

Signed by

Norman J. Quaine

Date

OCTOBER 19, 1995

Surveyor's Michigan License No.

33984