

SURVEY & DOCUMENTATION
1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION

2235- JAN 17 1996 **LAND CORNER RECORDATION CERTIFICATE**

LIBER 316 PAGE 318

For corners in **COMMISSION** Filing Requirement of Act 74, Mich. P.A. 1970
PRESQUE ISLE Located In: Corner Code #

PRESQUE ISLE COUNTY
RECORDED

95 OCT 20 PM 4:35

Jane M. Lambert
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>36N</u> R <u>2E</u>	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Ronald Bischer, in a field survey on August 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GL0 Notes - 1856 Resurvey	S73°W 38.68' 5" Oak
Geo. H. Cannon	02-06-75 - Delmar E. Porter #15410
Set wood post	same information as 02-04-75
Y. Pine 18" N27½°W 41 lks	
Y. Pine 16" S64°E 32 lks	11-19-87 - Delmar E. Porter #15410
02-04-75 - Delmar E. Porter #15410 Found 1" Pipe	1" Pipe
N13°E 53.16' 12" N. Pine	N13°E 52.80' N. Pine
S50°E 39.33' 5" Oak	S73°W 38.55' 5" Oak
	S50°E 39.25' 5" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pipe, set ½" Rod and Cap #22428 inside of pipe.
 S52°E 39.33' 8" Oak
 S71°W 38.68' 8" Oak
 N13°E 52.80' old Norway stump



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

½" Rod and Cap #22428 in 1" pipe
 S52°E 39.33' 8" Oak
 S71°W 38.68' 8" Oak
 N35°W 37.34' 5" White Pine
 N32°E 37.40' 4" Oak

Nails with witness tag #22428 used.

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *[Signature]*
 Date 9/20/95

Signed by Ronald R. Bischer

Date Oct. 3, 1995

Surveyor's Michigan License No. 22428