

2241

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 324

For corners in PRESQUE ISLE (County) Located In: Corner Code #

- 1. Public Land Survey T 36N R 2E M-6
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

PRESQUE ISLE COUNTY RECORDED

95 OCT 20 PM 4:36

Jesse M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Ronald Bischer, in a field survey on August 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes - 1856 Resurvey N59°E 24.86' 5" Maple
 Geo. H. Cannon S72°E 24.23' 4" Spruce
 Set wood post
 W. Pine 12" S65°W 20 lks
 Spruce 8" N55°W 22 lks
 08-19-76 - Ronald R. Bischer
 #22428, Found 1/2" Rod and Cap #8318
 N32°W 24.48' 6" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rod, set cap #22428
 N34°W 24.28' 7" Maple
 N56°E 24.86' 8" Maple
 S72°E 24.23' Spruce died and fell over
 S32°E 57.40' 16" N. Pine - blazed
 N79°W 14.50' 10" W. Birch - blazed



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" Rod and Cap #22428
 N34°W 24.28' 7" Maple
 N56°E 24.86' 8" Maple
 S32°E 57.40' 16" Norway Pine
 N79°W 14.50' 10" White Birch

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Debra E. Porter*
 Date 9/20/95

Nails with witness tag #22428 used.

Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date Oct 3, 1995