

2042

1995 PRESQUE ISLE COUNTY, STATE OF MICHIGAN REMONUMENTATION
JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 316 PAGE 325

For corners in
PRESQUE ISLE
(County)

Located In:

Corner Code #

PRESQUE ISLE COUNTY
RECORDED

95 OCT 20 PM 4:36

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- | | | | | | |
|--------------------------------------|---|------------|---|-----------|-----|
| 1. Public Land Survey | T | <u>36N</u> | R | <u>2E</u> | M-7 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald Bischer, in a field survey on August 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes - 1856 Resurvey	monument box
Geo. H. Cannon	N36°E 42.75' 8" J. Pine
Set wood post	N67°E 69.96' OBT stump
Sp. Pine 10" S55°W 56 lks	S67°W 99.98' 16" N. Pine
Y. Pine 16" N57½°W 24 lks	N65°W 93.95' 12" N. Pine
Y. Pine 20" N67°E 1.06 ch	
S. Pine 7" S70°E 1.01 ch	

10-03-75 - Delmar E. Porter
Set 4" Concrete monument in

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument in monument box, set cap #22428.
N71°W 93.95' 15" N. Pine
N34°E 42.75' 9" J. Pine
N67°E 69.96'
1.06 ch N. Pine OBT stump



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Concrete monument with cap #22428 in monument box
N71°W 93.95' 15" Norway Pine
N34°E 42.75' 9" Jack Pine
S02°W 33.66' 4" Norway Pine
S61°E 76.54' 6" Norway Pine

Nails with witness tag #22428 used.

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmar E. Porter*

Date 9/20/95

Signed by Ronald R. Bischer

Date Oct 3, 1995

Surveyor's Michigan License No. 22428