

State of Michigan Remonumentation Program
For Presque Isle County

PRESQUE ISLE COUNTY
RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 23 AM 10:10

For corners in

PRESQUE ISLE
(County)

Located In:

Corner Code #

- | | | | | | | |
|---------------------------------------|---|------------|---|-----------|-------------|-------|
| 1. Public Land Survey | T | <u>36N</u> | R | <u>2E</u> | <u>M-12</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling
in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Janet M. Lamb
REGISTER OF DEEDS

LIBER **310** PAGE **929**

Register of Deeds Stamp & File Number

I, Ronald Bischer, in a field survey on May 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|----------------------------------|------------------------------|
| 1856 Resurvey - GLO Notes | 10-30-79 - Ronald R. Bischer |
| Set Wood Post | ½" Rod |
| Hemlock 18" S67½°W 14½ links | N43°W 25.73' 10" Maple |
| Hemlock 14" N32°W 5 links | N56°E 12.96' 5" Maple |
| | S58°E 33.71' 13" Birch |
| 10-18-79 - Ronald R. Bischer | |
| Set ½" Rod by Single proportion. | |
| N43°W 25.73' 10" Maple | |
| N56°E 12.96' 5" Maple | |
| S58°E 33.71' 13" Birch | |


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found ½" Rod and Cap #15410
N53°E 12.96' 7" Maple
S58°E 33.71' 18" White birch
N43°W 25.73' 10" Maple
found stump w/foot blaze

SURVEY &
REMONUMENTATION

SEP 09 1994

COMMISSION *



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ½" Rod and Cap #15410
N53°E 12.96' 7" Maple
S58°E 33.71' 18" White birch
S87°W 16.09' 5" Fir
N67°W 25.24' 5" Fir

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Delmus & Porter*

Date July 27, 1994

Witness tags w/nails used.

Signed by Ronald R. Bischer

Date July 20, 1994

Surveyor's Michigan License No. 22428