

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 36N R 3E</u>	<u>B-11</u>
	<u>T 36N R 3E</u>	<u>B-13</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Carl T. Kiiskila, in a field survey on July 19, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11		●											
12		31		32		33		34		35		36	
13		●											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-11 GLO – G.H. Cannon set quarter section post, 1856.
Wit: B. Ash 13" N 57° E 8 links
B. Ash 10" S 52° W 13 links

B-13 GLO – John Hodgson set Hemlock 10" in diameter for quarter section post in 1840. No other witnesses recorded.

Delmer Porter, on 11-09-79, found a 2" pipe and replaced it with a concrete monument and brass cap.

Wit: Fence post N 26° E 35.16'
6" twin Birch S 28° E 41.67'
3" W. Pine S 17° W 19.35'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 Reestablished the North quarter corner of Section 31 online between the Northeast corner and the Northwest corner of Section 31 prorated to U.S. runout.

B-13 Found a standard Presque Isle County concrete monument with a brass cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 Set a standard DNR monument and carsonite marker post.
Wit: Set nail in 20" Ash N 45° E 26.89'
Set nail in 16" Ash S 52° E 14.93'
Set nail in 4" Ash S 3° E 30.84'
Set nail in 8" Ash N 65° W 34.42'
Centerline of east-west powerline right-of-way North 320'
Carsonite post North 1'

B-13 Found a Presque Isle Co. concrete monument with brass cap. Set a carsonite marker post.

Wit: Set nail in 8" Oak N 22° E 28.08'
Set nail in 10" W. Pine N 72° E 60.18'
Set nail in 11' W. Pine S 60° E 44.18'
Set nail in 9" R. Pine S 1° E 20.22'
Set nail in fence post N 23° E 35.70'
Carsonite post North 33'
Monument falls in center of east-west dirt road.

Signed by Carl T. Kiiskila
Surveyor's Michigan License No. 33981



Date 8-2-99