

Eng Division

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>36</u> N. R. <u>4</u> W.	B-11; C-11; C-10
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, KENNETH J. OSTLING, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on NOVEMBER 1, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-11 - FOUND OLD POST AT CORNER, WITHIN 5FT OF PROPORTIONATE MEASUREMENT, APPARENTLY USED IN ADJACENT SURVEYS ALTHOUGH ORIGIN IS UNKNOWN. CONSIDERED BEST AVAILABLE EVIDENCE OF PROPER LOCATION.
- C-11 - SET CORNER RELATIVE TO N 1/8 AND SE CORNER SECTION 31. FALLS IN LINE WITH OLD SURVEY LINE WEST, BUT COULD LOCATE NO PREVIOUS MONUMENT.
- C-10 - SET BY PROPORTIONATE MEASUREMENT BETWEEN SECTION CORNERS. COULD LOCATE NO PREVIOUS CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11			C-11			C-10		
DNR MONUMENT			SET 5/8" IRON BAR W/CAP			DROVE 5/8" BAR W/CAP		
7" CEDAR	N58°E	12.7'	12" HEMLOCK	WEST	36.0'	12" CEDAR	S64°W	28.8'
6" CEDAR	S60°E	13.3'	7" CEDAR	N72°E	41.9'	7" CEDAR	S58°E	40.0'
6" SQ. CEDAR	S70°E	1.8'	4' WEST OF CENTER LINE CO. ROAD					

SIGNED BY *Kenneth J. Ostling* DATE 2/16/84
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ PRESQUE ISLE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET