

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
PRESQUE ISLE  
(County)

Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>36N</u>	R	<u>4E</u>	<u>L-11</u>		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	<u>25</u>	T	<u>36N</u>	R	<u>4E</u>	<u>12</u>
	S	_____	T	_____	R	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on January 21, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

L-11 GLO G.H. CANNON 1856 SET POST  
WITNESS: BEECH 14° N45°E 36 LKS  
BEECH 16° N40°W 18 LKS  
CO. SURVEYOR G.F. DELAMATER RLS #2674  
NO DATE SHOWS A 1/2" BAR IN COR.  
LIBER 202, PAGE 524 D. PORTER LS#15410  
SHOWS A 1/2" PIPE FOR CORNER

12- FREDERIC LOUD REGISTERED CIVIL ENGINEER 1928  
SET A PLAT MON. AT THE SOUTHWEST COR. OF GOV.  
LOT 3. ALSO THE SOUTHWEST CORNER OF THE  
SUPERVISOR'S PLAT OF SACRED ROCK PARK LIBER 1  
PAGE 125.

WIT: 5° NORWAY N5°E 51.35'  
6° W. PINE S5°E 30.80'  
6° BIRCH S20°W 34.20'

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

L-11 FOUND A 3/4" ROD IN A MON. BOX  
FITTING D. PORTER WITNESSES  
AND HIS DISTANCES NORTH AND WEST.  
ALSO FITS G.F. DELAMATER DISTANCES.

12- FOUND A CONCRETE PLAT MON. FITTING THE WEST  
LINE OF SACRED ROCK PARK REASONABLY WELL.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-11 FOUND 3/4" ROD IN MON. BOX  
WITNESS: 30" MAPLE N19°E 57.09'  
20" SCOTCH PINE S22°E 51.07'  
14" W. BIRCH S41°W 34.47'  
7" ELM N26°W 32.44'

12- FOUND A CONCRETE PLAT MONUMENT  
WITNESS: 12" HEMLOCK N16°E 28.08'  
7" W. PINE N34°W 15.27'  
14" TWIN OAK S68°W 31.29'  
10" TWIN MAPLE S15°W 53.54'

Signed by: Carl T. Kiiskila Date: 2-2-99

Surveyor's Michigan License No.: 33981

