

SURVEY &  
REMONUMENTATION

APR 07 1998

SECTION

9210

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in <u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>1W</u>	<u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling S _____ in Section T _____	T _____ R _____	_____
3. Miscellaneous S _____ Property in Sec. S _____	T _____ R _____	_____

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

16 DEC 97 10:16 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gerald J. Gray, in a field survey on June 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- WM A. Burt, 1850  
Y. Pine 18 N45E 45  
Y. Pine 18 S73W 44
- G.F. Delamater, 8/8/1935, Found Gov. B;s, set pipe in conc. (L.. 1, P. 99)  
W. Pine St. 36, S54E 24.7'  
W. Pine St. 30, S31E 61.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" iron pipe in concrete  
Found stump remains of both Delamater witnesses and one GLO B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set Standard Roscommon County Monument

- |          |           |              |
|----------|-----------|--------------|
| Set Nail | 6" W. Oak | N75°W 16.55' |
| Set Nail | 8" B. Oak | N30°E 30.15' |
| Set Nail | 6" R. Oak | S43°E 30.78' |
| Set Nail | 8" Maple  | S52°W 57.67' |

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3		●										
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE MAY 17, 1998  
*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Signed by Gerald J. Gray Date \_\_\_\_\_  
Surveyor's Michigan License No. 17741



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 4444