

8940 8 1994

ROSCOMMON COUNTY REMONUMENTATION

Dec 16 9 19 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Robert L. Cavanagh
REGISTERED SURVEYOR

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T21N, R1W	C-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 11-30-93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
W/post placed by Wm A. Burt 1850 1975± Liber 2 corner record
Y. Pine 12" N52°W 33 Lks 1" x 24" pipe
W. Pine 24" S65°E 35 Lks BT 18" W. Oak N64°E 33.0
1947 George D. Henning land survey BT 18" W. Oak S80°W 47.5
1"x24" pipe in corner BT 18" Pine Stp S88°E 51.3
BT W. Oak 18" N64°E 33.0 Steel fence post at corner
BT W. Oak 18" S8°W 47.5
BT Pine Stp 30" S88°E 51.3
Steel fence post in corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found pipe and Henning 1947 witness
W. Oak NE
W. Oak S8°W
Accepted as the best available evidence of the position of the original corner.
See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Roscommon Co. Std. Mon stamped C-7 17614
N64°E Nail & tag in 22" W. Oak 33.35
S67°E Nail & tag in 20" R. Oak 62.42
S08°W Nail & tag in 30" R. Oak 48.30
N50°W Nail & tag in 9" B. Oak 34.34
Carsonite post North 1.64



Signed by *Larry L. Cavanagh* Date 12-15-93
Surveyor's Michigan License No. 17614

Date November 30, 1993 Peer Group Approved