

8941

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

DEC 16 9 19 AM '93

COMMISSION

For corners in

Table with columns: Roscommon (County), Located In: (Town/Range), Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 11-30-93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (8,20) contains a star symbol.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

W/Post placed by Wm A. Burt 1850
Y. Pine 24" S72°W 10
Birch 16" N18°E 27
1941 Land Corner Record
Set 3/4"x24" pipe about 3' Sp. of Wheel Tract
of E & W Road (Set from original Wit.)
Marked Maple 12" N19°W 122.5
Marked Maple 10" N15°E 118.5
NOTE: Distances in 1980 survey are believed to vary 1941 location, although pipe is called different diameters at different visits, it's concluded that the pipe is undisturbed and is in fact same pipe set

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pinched Pipe
Fd all 1993 Wit
Beech Clump (1980)

And is accepted as a careful and faithful perpetuation of the position of the original corner.

See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon Co. Std Mon Stamped C-8 17614
S69°W Nail & tag in 15" Beech(Clump) 27.56
S09°W Nail & tag in 14" R Pine 31.35
S30°E Nail & tag in 10" Poplar 46.74
N38°W Nail & tag in Fence Post 57.70
N60°E Nail & tag in Maple Clump 35.35



Signed by [Signature]
Surveyor's Michigan License No. 17614

Date 12-15-93

Date Nov 30, 1993 Peer Group Approved