

SURVEY &  
REMONUMENTATION

APR 07 1998

SECTION

9203

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in <u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>1W</u>	<u>D-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

16 DEC 97 10:15 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gerald J. Gray, in a field survey on May 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:

G.F. Delamater 1935 L. 1., P. 99  
Set 5/8" iron rod  
S. Pine 10, S49E 7.6'  
B. Oak 8, S48W 23.3'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Dec 5, 1997

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron rod

Dead pine tree with Delamater witness tag at S50°E 7.70' being used as fence corner.

D-1 in Lake

D-2 to D-3 S00°21'46"E 2625.66

D-2 to 1/8 corner S89°09'40"E 1317.16, 1/8 corner to E-2 S89°08'57"E 1318.83

C-2 in Lake


- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Roscommon County Monument

Set Nail	6" Pin Oak	N10°E 25.50'
Set Nail	14" W. Oak	N35°E 30.28'
Set Nail	6" Jack Pine	S05°W 33.09'
Set Nail	4" Jack Pine	West 9.80'

Signed by Gerald J. Gray Date \_\_\_\_\_

Surveyor's Michigan License No. 17741



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 429