

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION
9211

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in <u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 1W	D-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 10:16 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gerald J. Gray, in a field survey on April 7, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- WM A. Burt, 1850
Y. Pine 14, N67E 24
Y. Pine 14, S30W 39
- G.F. Delamater, 8/8/35, Found both Gov. B's & P., Set Pipe in Conc. (L. 1, P. 99)
W. Oak 4, N48°W 41.4'
W. Oak 8, S5E 90.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found burnt stub of wood stake at intersection of old witnesses.

Replaced with Iron.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Roscommon County Monument

- | | | |
|----------|------------------|--------------|
| Set Nail | 15" W. Oak | N48°W 41.25' |
| Set Nail | Twin 12" W. Oak | S05°E 91.30' |
| Set Nail | 10" B. Oak | S52°W 19.47' |
| Set Nail | Quad. 15" B. Oak | S83°E 24.46' |
| | Pine Stump | N67°E 15.8' |
| | Pine Stump | S30°W 25.7' |

Signed by Gerald J. Gray Date _____

Surveyor's Michigan License No. 17741


A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3			•									
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE May 17, 1998

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 445