

SURVEY & REMONUMENTATION

APR 07 1998

**SECTION
9246**

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970**

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

16 DEC 97 12:26 P.M.

I. Public Land Survey

Located in:	Corner Code #
T21N R1W	D-7
T_____R_____	_____
T_____R_____	_____
T_____R_____	_____

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM A. BURT 1850 SET POST ASPEN 9" S37°W 16 LKS W. BIRCH 6" N60°W 2 LKS	LCRC LIBER 2, PAGE 17 1970'S SAME AS ABOVE
G.D. HENNING 1947 SET 1" X 24" PIPE AT SINGLE PROPORTIONATE DIST. WIT: 3" CHERRY N40°E 95.0' 3" CHERRY S46°E 18.4' 4" W. BIRCH S78°W 17.0'	LARRY CAVANAGH APRIL 1997 UNRECORDED SURVEY FD 1" PINCHED PIPE 10" MAPLE N35°E 8.10' 12" MAPLE S25°W 20.10' 14" W. BIRCH S78°W 16.75' 7" MAPLE N40°W 20.72' SINGLE WIRE FENCE NORTH 13'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7		•											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PINCHED PIPE (HENNING)
FOUND 4" W. BIRCH S78°W (NOW 14")

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614
NAIL & TAG IN 10" MAPLE N35°E 8.10'
NAIL & TAG IN 12" MAPLE S25°W 20.10'
NAIL & TAG IN 14" W. BIRCH S78°W 16.75'
NAIL & TAG IN 7" MAPLE N40°W 20.72'
SINGLE WIRE FENCE NORTH 13'
CARSONITE POST NORTH 0.5'


THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 5, 1997**

Marvin E. Myers ME MS
**Marvin E. Myers, P.S.
County Surveyor**

Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date *Dec. 11, 1997*



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 471