

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION
9216

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 10:18 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For Corners In Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 1W	E-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gerald J. Gray, in a field survey on May 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Wm. A. Burt 1850
Spruce Pine 14 S80E 58
Spruce Pine 8 N65W 20
- G.F. Delamater 1935 L. 1., P. 99
Set pipe in conc.
B. Oak 12, S49W 75.5'
B. Oak 12, S60E 77.5'

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE MAY 17, 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" pipe in concrete 1' below ground surface. No evidence of occupation or previous witnesses.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Roscommon County Monument

- Set Nail Twin 14" Pin Oak Due North 26.85'
- Set Nail 6" Red Pine N61°E 25.10'
- Set Nail 8" Aspen S14°W 9.40'
- Set Nail 6" Jack Pine N81°W 39.65'

Signed by Gerald J. Gray Date _____

Surveyor's Michigan License No. 17741



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 450