

**SURVEY &
REMONUMENTATION**

APR 07 1998

**SECTION
9244**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in
Roscommon County

16 DEC 97 12:26 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

1. Public Land Survey

Located in:	Corner Code #
T21N R1W	E-8
T_____R_____	_____
T_____R_____	_____
T_____R_____	_____

FILE IN LIBER 3 OF LAND CORNER

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

WILLIAM A. BURT 1850
SET POST
CEDAR 6" S48°E 18 LKS
W. BIRCH 6" N50°W 10 LKS

LARRY CAVANAGH APRIL 1997
UNRECORDED SURVEY
FD 1/2" X 30" STEEL BAR
16" CEDAR N63°E 36.98'
16" CEDAR S45°E 15.30'
12" CEDAR N35°W 13.10'
11" MAPLE S17°W 14.55'

G.F. DELAMATER 1935
SET 1/2" X 30" STEEL BAR
FROM GLO WITNESS
CEDAR 8" N63°E 37.2'
CEDAR 5" N35°W 13.3'

LARRY L. CAVANAGH MAY 1997
UNRECORDED SURVEY
SAME AS ABOVE

G.D. HENNING 1941
SAME AS ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND DELAMATER 1/2" X 30" STEEL BAR
BOTH CEDAR WITNESSES (USED SEE BELOW)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614
NAIL & TAG IN 16" CEDAR N63°E 36.98'
NAIL & TAG IN 16" CEDAR S45°E 15.30'
NAIL & TAG IN 12" CEDAR N35°W 13.10'
NAIL & TAG IN 11" MAPLE S17°W 14.55'
CARSONITE POST NORTH 1.3'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE DEC 5, 1997**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date *Dec. 11, 1997*

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 469