

9536

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 07 1998

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

SECTION

29 DEC 97 3:48 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

For Corners in Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 1W	H-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Gerald J. Gray, in a field survey on June 22, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. G.F. Delamater, 1935, Set 3/4" pipe at intersection of 1/4 lines
W. Oak 5, N30W 27.9'
B. Oak 3, S10W 7.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron pipe (1" o.d.) and both Delamater witnesses.
H-3 to H-2 N00°04'43"E 2625.92
H-2 to H-1 N00°11'26"E 2699.60
G-2 to H-2 S89°04'18"E 2635.50
H-2 to I-2 S89°55'00"E 2566.20

ROSCOMMON COUNTY

PEER GROUP APPROVAL

DATE DEC 5, 1997

Marvin E. Myers M.E.S.

Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set Standard Roscommon County Monument

- Set Nail 16" W. Oak N29°W 28.04'
- Set Nail 14" B. Oak S17°W 8.03'
- Set Nail 8" R. Oak N58°E 18.12'
- Set Nail 6" R. Oak S64°E 28.95'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Gerald J. Gray Date _____

Surveyor's Michigan License No. 17741



APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993

LIBER 3 PAGE 488