

11718

Roscommon County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

\_\_\_\_\_ Roscommon \_\_\_\_\_ Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T21N R01W M-2  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

FILE IN LIBER 3 OF LAND CORNERS  
STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

29 DEC 98 2:18 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SURVEY &  
REMONUMENTATION

MAR 01 1999

SECTION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Timothy L Lapham, in a field survey on September, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

M-2: GLO 1838 J Brink set post  
White Oak 10 S53-1/2W 31  
White Oak 10 N62W 10

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Dec 4, 1998

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2: Found large spike 3'+/- East of centerline of trail road (fire trail) at post to East, tree with wire in it to East and remains of old post to West. No evidence of GLO corner found. Rejected found spike due to lack of history. Decided to set corner by single proportionate measure between accepted A-1 and A-3 of T21N R1E. Accepted SPM corner position as best available method of reestablishing corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2: Set 5/8"x36" rod with aluminum Ogemaw county remonumentation cap witnesses:  
West 2'+/- centerline of north and south trail  
S76E 4.50 spike in north face of cedar post  
S33W 30.05 spike in SE face of 14" oak  
S48E 14.69 spike in NE face of 18" oak  
S79W 33.58 spike in S face of 18" poplar  
N43E 15.72 spike in NW face of 18" oak

Signed by *Timothy L Lapham*  
Surveyor's Michigan License No. 27595

Date 12/23/1998