

11717

Roscommon County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Roscommon _____ Located in: _____ Corner Code # _____
(County)

1. Public Land Survey T21N R01W M-3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILE IN LIBRARY STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

29 DEC 98 2:18 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Timothy L Lapham, in a field survey on September, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

M-3: GLO 2/13/1837 J. BRINK POST
BEECH 8" S37W 33LK
MAPLE 9" N76W 06LK

GLO 5/27/1846 B.F.HALL FOUND POST
W. PINE 14" S12E 21LK
SUGAR 6" N15E 28LK

GLO 8/26/1850 G H CANNON FOUND POST
NO ADDITIONAL WITNESSES

DNR CIRCA 1920 M. SCHAAF - RECORDS INDICATE THAT
CORNER WAS FOUND BUT NOT REPLACED BUT RECORDS
DO NOT SHOW ANY CORNER MATERIAL OR WITNESSES

ROSCOMMON CO. L2-LCRC-P11 DATE AND SURVEYOR

UNKNOWN
1/2" IRON IN CENTERLINE ROADS
S56E 41.0' 8" R. OAK (1)
S37W 38.5' 4" TW. MAPLE
N64W 43.5 8" R. OAK (2)

SURVEY 11/6/1961 G HENNING
1/2" IRON BAR IN CENTERLINE ROADS AT INTERSECTION
FIRE LANES WITH SAME ACCESSORIES AS ROSCOMMON
LCRC 2-11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3: FOUND 1/2"X18" REROD IN APPROXIMATE CENTERLINE OF TRAILS N-S-W. MATCHES PREVIOUS WITNESSES (1) AND (2).
ACCEPTED IRON AS BEST AVAILABLE EVIDENCE OF CORRECT CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3: Set 5/8"x36" rerod with aluminum Ogemaw County remon cap to 8" below grade.(road is being eroded by vehicles)

Witnesses:

S53E 41.22' NAIL IN 10" OAK (OBT)
N50E 40.92' NAIL IN 8" MAPLE
N13W 52.37' NAIL IN 18" OAK
N59W 43.43' NAIL IN 18" OAK (OBT)
EAST 8'+/- carsonite post

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 9, 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

Date 12/21/98

Signed by *Timothy L Lapham*
Surveyor's Michigan License No. 27595