

11710

Roscommon County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| _____ Roscommon _____ (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T21N R01W | M-10 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

FILE IN LIBER 3 OF LAND CORNERS
STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

29 DEC 98 2:16 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy L Lapham, in a field survey on September, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Witness Sheet 1985 D Ledy
Accessories same as Ogemaw LCRC 1-152

M-10: GLO 2/12/1837 J Brink set post
Hemlock 8 S40W 15
W Pine 9 N50W 21

Ogemaw Co. LCRC 1-152 3/12/1976 N Caldwell
set 1/2" bar and cap in 3/4" pipe
S24W 21.6' 9" R Oak (1)
N57E 41.7' 8" Cherry (2)
S40W 9.90' Remains of 8" Hemlock (3)

Survey 3/11/1976 N Caldwell
Accessories same as Ogemaw LCRC 1-152

Sec. Break not dated from Wade Trim
no corner description or accessories

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 1, 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-10: Found 1/2" rod inside 3/4"x18" pipe. Witnesses: (2) found dead stub; (3) found remains of stump with species undeterminable.
Accepted found iron as perpetuation of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-10: Set 5/8"x36" rod with aluminum Ogemaw county remon cap.

Witnesses:
N37W 21.60' NAIL IN 18" MAPLE
N34E 31.22' NAIL IN 24" MAPLE
N87E 21.71' NAIL IN 10" MAPLE
S05E 9.05' NAIL IN 10" ASH
South 1'+/- carsonite post

SURVEY &
REMONUMENTATION

MAR 01 1999

SECTION

Signed by *[Signature]*
Surveyor's Michigan License No. 27595

Date 12/21/98