

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 21 N.R. 3 W


Roscommon COUNTY

DESCRIPTION OF CORNER 1/4 corner on S. side Section 31, on 2nd correction line

CORNER MONUMENT Set 1" pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 22, 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" Cedar N 3 E 7.7'

5" Balsam West 26.7'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between restored section corners. Could not find definite U.S. evidence. Found a squared post about 25 links south which we believe to be tally markers from a previous survey during C.C.C. days.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostberg* DATE June 22, 1966
REGISTERED LAND SURVEYOR

#10068