

3898

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

19 MAY 98 11:09 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

|      |     |       |
|------|-----|-------|
| T22N | R3W | H-13  |
| T21N | R3W | H-1 ✓ |
| T    | R   |       |
| T    | R   |       |

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNER  
Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838  
PITCH PINE 8 N41E 18  
PITCH PINE 8 N47W 28

DNR 1930'S  
FOUND OLD CORNER  
NO TREES FOR NET

SCHAAF INDICATES STAKE  
SET IN PREPARATION FOR  
IRON

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2" PIPE WITH 8" SQUARE CORE BASE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614  
WIT: NAIL & TAG IN 11" NORWAY N80°E 94.15'  
NAIL & TAG IN 11" B. OAK S69°E 47.92'  
NAIL & TAG IN 2" B. OAK S32°W 34.87'  
NAIL & TAG IN 10" NORWAY N60°W 47.20'  
CARSONITE POST NORTH 16.3'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

SURVEY &  
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE MAY 15 1998

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor

Signed by Larry L. Cavanagh Date May 16, 1998  
Surveyor's Michigan License NO. 17614



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983