

3900

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

For corners in  
Roscommon County

19 MAY 98 11:10 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

1. Public Land Survey

Located in:	Corner Code #
T22N R3W	J-13
T21N R3W	J-1 ✓
T R	
T R	

FILE IN LIBER 3 OF LAND CORNE  
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838 SET POST WHITE PINE 10 N59W 38 PITCH PINE 10 N4E 8	LCRC 1970'S, L2, P250 1/2" BAR 7' B. OAK N45W 28.9' 14" B. OAK S20W 25.3'
DNR 1930'S FOUND U.S. BEARINGS NO TREES FOR N.B.T.	LARRY L. CAVANAGH 1974 SECTION SUB-DIVISION SURVEY SET 1/2" X 18" STEEL BAR SAME WITNESSES AS ABOVE
SCHAAF INDICATES STAKE SET IN PREPARATION FOR IRON	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" STEEL BAR  
FOUND 14" B. OAK S20W 25.3'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614  
WIT: NAIL & TAG IN 14" B. OAK S32°E 23.85'  
NAIL & TAG IN 9" NORWAY S20°W 25.64'  
NAIL & TAG IN 8" NORWAY N45°E 59.11'  
NAIL & TAG IN 13" NORWAY S38°E 77.04'  
CARSONITE POST N21°W 23.47'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

SURVEY &  
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE MAY 15 1998

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh* Date MAY 16, 1998  
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983