

3903

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

19 MAY 98 11:10 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N	R 3W	M-13
T21N	R3W	M-1 ✓
T22N	R2W	A-13
T21N	R2W	A-1

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration

JOHN BRINK 1838
SET POST CORNER
MAPLE 10 N70E 11
WHITE PINE 12 N45 1/2W 50

DNR 1930'S
FOUND U.S. BEARINGS
NBT
W. PINE STUMP 30 N26W 89 1/2
W. PINE STUMP 24 N44 3/4E 60

KENNETH J. OSTLING, LCRC 1974
L1, P105
SET 3/4" X 36" BAR
N-S POWER LINE W 56.5
9" CEDAR N85E 34.6
30" W. PINE N35E 52.9

LCRC 1970'S, L2, P251
SAME WITNESSES AS ABOVE

SCHAAF INDICATES FOUND
AND SET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO ORIGINAL EVIDENCE
FOUND 1" X 20" STEEL ROD
FOUND BOTH CEDAR AND W. PINE WITNESSES FROM 1974

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614
WIT: NAIL & TAG IN 11" CEDAR N85°E 34.65'
NAIL & TAG IN 37" W. PINE N38°E 54.13'
NAIL & TAG IN POWER POLE N81°W 57.18'
CARSONITE POST S55°W 2.43'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &
REMONUMENTATION


OCT 05 1998

SECTION

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 11/15/98

Marvin E. Myers

Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date

May 16, 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 514