

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Roscommon _____
 (County)

- | | | | |
|--------------------------------------|---------|---------|-----------|
| 1. Public Land Survey | T _____ | R _____ | F13 _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | R _____ | _____ |
| | S _____ | R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ | R _____ | _____ |
| | S _____ | R _____ | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 9, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- F13 - GLO - Set 1/4 post - J. Brink - 1837
 Y. Pine 8" N51°E 25 L.
 Aspen 10" N51½°W 51 L.
 - Beiknapp - Fd. US bearings down. No trees for NBT
 - M. Schaaf - 1921 - Run S. Line of Sec. 33
 - K. J. Ostling - 1966 - Fd. 2" Pipe, 6" R. Pine N24°W 45.2'
 5" W. Pine N40°E 49.5'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F13 - Standard ¼ Corner Common to Sec. 33, T21N, R3W - Found 1 ¾" I.D. Iron pipe stub in Conc. Block, leaning W'y - 5' S. of CL. E-W Gravel Road and in line w/ firelane N. Standard Schaaf Monument in area. Appears to have been set by Schaaf midway between 'E13' & 'G13'. Flts stumps of Ostling's BT's. Schaaf 1 ½" pipe in concrete accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F13 - Replaced Schaaf mon. w/ 4" DOC (DNR) Brass Cap on 1" x 36" long galv. Iron pipe w/ tin can w/ conc. around cap - Down 0.7'
 N57°W 108.71' to N & T in NE side 13" W. Pine scribed 'XBT'
 N60°E 116.09' to N & T in NW side 8" W. Pine scribed 'XBT'
 S57°E 106.86' to N & T in SW side 11" W. Pine scribed 'XBT'
 S22°W 68.89' to N & T in W side 7" W. Pine scribed 'XBT'
 Set Blue Carsonite Post w/ Loc. tag N45°W 40'
 S89° 32.44' E 722.74' (Grid) to F1 - T20N, R3W

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/3/2003

