

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Roscommon _____
 (County)

1. Public Land Survey T 21N R 3W G13
 T _____ R _____
 2. Property Controlling S _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

1. Craig W. McVean, in a field survey on June 9, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- G13 - GLO - Set post - J. Brink
 Y. Pine 16" N74½°E 37 L.
 W. Oak 10" N6°W 48 L.
 - Belknapp - Est. Corner - NBT WPS 36" N6°W 33 L.
 - M. Schaaf - 1921 - Chain E from "E13" @ 80.08 we intersect Norway and W. Oak tree possible BT. 105 L. S. of line.
 - K. J. Ostling - 1966 - Fd. 1½" pipe; 10" Oak N41°W 43.3' 12" Oak N54°E 47.2'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G13 - Standard Sec. Cor. Common to Sec. 33 & 34, T21N, R3W - Fd. 1½" I.D. Iron pipe stub in Conc. Block in CL. of E-W Gravel Road. Standard Schaaf monument in area. Fit's Stumps of Ostlings BT's. Schaaf indicates he had possible GLO BT's here. Schaaf 1½" pipe in conc. accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G13 - Replaced Schaaf Mon. w/ 4" DOC (DNR) Brass Cap on 1" x 36" Galv. Iron pipe w/ tin can w/ conc. around cap - Down 0.8';
 N31°E 48.10' to N & T in W. side 15" W. Pine scribed 'XBT'
 N41°W 45.69' to N & T in NW side 4" Oak scribed 'XBT'
 N61°W 76.33' to N & T in N side 1½" W. Pine scribed 'XBT'
 S54°E 45.51' to N & T in NE side UP
 Set Blue Carsonite Post w/ Loc. tag 33' North
 S89° 58.10" E 754.13' - Grid Dist. (754.38') to Closing Corner - G1, T20N, R3W
 GLO

Signed by: Craig W. McVean Date: 12/3/2003

Surveyor's Michigan License No.: 39088

