

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION



# LAND CORNER RECORD

T. 21 N.R. 3 W ✓  
T. 21 N.R. 4 W


Roscommon COUNTY

DESCRIPTION OF CORNER Town corner common to Sections 31-36 on 2nd correction line

CORNER MONUMENT Set 1" pipe with 4" Aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 22, 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

6" S. Maple N 37 W 16.7'

6" R. Oak N 40 E 17.9'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement of the correction line in this township. Set corner by single proportionate measurement between good corners one mile east and one-half mile west. Nothing left for U.S. evidence, or any other previous corner.

SURVEYOR'S SEAL

SIGNED Kenneth J. Osting DATE June 23, 1966  
REGISTERED LAND SURVEYOR #10026