

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ROSCOMMON

	(County)	Located In:	Corner Code #/
1.	Public Land Survey	T <u>21N</u> R <u>4W</u>	<u>C-13</u>
		T _____ R _____	<u>D-13</u>
		T _____ R _____	<u>E-13</u>
		T _____ R _____	
2.	Property Controlling in Section	S _____ T _____ R _____	
		S _____ T _____ R _____	
3.	Miscellaneous Property in Sec.	S _____ T _____ R _____	
		S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL F. ROSER, in a field survey on JUNE 20, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>C-13</u>	<u>C-13(CONT)</u>	<u>D-13</u>	<u>E-13</u>
		(*C* CONT.)	
		N 1/4 S-5	
		T20N-R4W 589 10'E 441.92'	



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>C-13</u>	<u>C-13(CONT)</u>	<u>D-13</u>	<u>E-13</u>
M. SCHAAF, DEPT FORESTRY CHIEF & RLS (NOW DECEASED) HAD BOTH USBT STUMPS; SEE HIS PENCIL ADDITIONS TO 1936 CONSERVATION DEPT LEATHER BOUND BOOK OF GLO LINE NOTES, T20N-R4W. COR FALLS ON SLIGHTLY HIGH GRD, SOME MAPLE & POPLAR; BUT IT IS LOW & SWAMPY ALL AROUND. N.	SCHAAF WAS ORIG'LY AT THIS COR ON JULY 9, 1915; HE SAYS *BOTH HEMLOCK (USBT'S) STUMPS FOUND*. COR FITS 1837-GLO TIE WEST TO TOWN LINE CREEK (26.25 CH'S, TO NEAREST 1/4 CHAIN -1733'), 1742'± MEA. THIS SURVEY.	RECOVERED OLD 1 1/2" X 42" PIPE FOR S 1/4 S-32; WAS PROBABLY SET BY MARCUS SCHAAF (CONS. DEPT SURVEYOR /FORESTER) IN 1930'S. FD STP REMAINS & PIECE OF SHELL OF U.S TAMARACK BT W/PARTIALLY OVERGROWN BLAZE W/VISIBLE SCRIBING. COR FALLS IN SILT & WATER, TAMARACK-ALDER, SWP.	FD H. BELKNAP'S (1911) POST BOTTOM; FITS HIS NBT'S; (13" CED, N45W, 18.5' & HIS TAM 7" - STP REMAINS, N61°E, 7.3'). COR FALLS IN SWP W/LOTS OF MUCK & ICE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>C-13</u>	<u>C-13(CONT)</u>	<u>D-13</u>	<u>E-13</u>
FD M. SCHAAF 1 1/2" PIPE W/CONC BASE; REPL'D W/1" X 50" PIPE W/DNR CAP & SET CED POST.		FD 1 1/2" X 42" RUSTED OUT PIPE W/5" CUBE OF CONC. REPL'D BY PUSHING IN 1 1/2" X 86" PIPE W/1" X 30" GALV PIPE W/STD DNR CAP; SET CED POST.	FD BELKNAP (1911) POINTED CED POST BOTTOM. REPL'D W/PUSHED IN 1" X 7" GALV PIPE W/STD DNR CAP; SET CED POST.
12" MAPLE N84°W 29.6'		5" MAPLE N65°W 14.0'	8" TAMARACK N80°W 16.6'
10" MAPLE N60°W 56.9'		8" TAMARACK N35°E 57.2'	5" B SPRUCE N60°W 3.1'
16" MAPLE N04°W 24.5'		16" W PINE S20°W 32.6'	5" CEDAR N55°E 11.2'
11" CEDAR N80°E 38.8'		16" CEDAR S55°W 16.7'	6" CEDAR S70°E 11.4'
NW COR S-5 T20N-R4W N89°47'E 449.13'		(CONT. IN "A" SECTION)	NE COR S-5 T20N-R4W S88°46'E 446.12'

Signed by Carl F. Roser 01-11-90 Date _____
 12028

Surveyor's Michigan License No. _____