

3903

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T22N	R 3W	M-13
T21N	R3W	M-1
T22N	R2W	A-13
T21N	R2W	A-1 ✓

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

19 MAY 98 11:10 A.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

I, Larry L. Cavanagh, in a field survey April, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNER  
Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration

JOHN BRINK 1838	KENNETH J. OSTLING, LCRC 1974
SET POST CORNER	L1, P105
MAPLE 10 N70E 11	SET 3/4" X 36" BAR
WHITE PINE 12 N45 1/2W 50	N-S POWER LINE W 56.5
	9' CEDAR N85E 34.6
	30' W. PINE N35E 52.9
DNR 1930'S	LCRC 1970'S, L2, P251
FOUND U.S. BEARINGS	SAME WITNESSES AS ABOVE
NBT	
W. PINE STUMP 30 N26W 89 1/2	
W. PINE STUMP 24 N44 3/4E 60	

SCHAAF INDICATES FOUND  
AND SET

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO ORIGINAL EVIDENCE  
FOUND 1" X 20" STEEL ROD  
FOUND BOTH CEDAR AND W. PINE WITNESSES FROM 1974

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ROSCOMMON COUNTY MONUMENT STAMPED 17614  
WT: NAIL & TAG IN 11' CEDAR N85°E 34.65'  
NAIL & TAG IN 37' W. PINE N38°E 54.13'  
NAIL & TAG IN POWER POLE N81°W 57.18'  
CARSONITE POST S55°W 2.43'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SURVEY &  
REMONUMENTATION

OCT 05 1998

SECTION

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 11/15/98

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh* Date May 16, 1998  
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 514