

8943

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 16 9 19 AM '93

For corners in COMMISSION

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> , R <u>2W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Robert A. ...
REGISTERED
**ROSCOMMON COUNTY
PEER GROUP APPROVAL**
DATE 12-7-93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

W/post placed by Wm A. Burt 1850
B. Ash 16" S70°E 30 Lk
Hemlock 8" N55°W 43Lk
1990 Land corner recordation 11, P282
1/2"x18" capped steel bar in base of fence post, L. Cavanagh
S25°E 6" Maple 7.45
S49°W 6" Ash 6.55
N28°W 9" Maple 24.2
N10°E 4" Ash 15.6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" capped iron at base of old corner fence post. All 1990 witnesses, GLO swamp calls fit corner to North, South and West of this location, accepted as the best available evidence of the position of the original corner.

See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon Co. Std. Mon stamped K-7 17614
S25°E Nail & tag in 6" Maple 7.62
S49°W Nail & tag in 6" Ash 6.75
N28°W Nail & tag in 9" Maple 24.60
N10°E Nail & tag in 4" Ash 15.62
Carsonite post North 1.42



Signed by *Larry L. Cavanagh* Date 12-15-93
Surveyor's Michigan License No. 17614

Date December 7, 1993 Peer Group Approved