

8944 FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Dec 16 9 19 AM '93

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N, R 2W	K-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Robert H. ...
REGISTERED DEEDS

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

W/Post placed by Wm A. Burt 1850
Beech 12" S45°W 21
Beech 6" N35°E 18
1990 Land corner recordation L-1, P282
1/2"x18" capped steel bar, L. Cavanagh
S22°E 4" Poplar 69.87
N85°W 4" Poplar 32.2
N25°E 14" Maple 98.55
N65°E Spike in Cor Fence Post 69.1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" capped iron
All 1990 Witnesses
A new fence runs West & South of this corner. Appears to be built on a 4' offset South of & West of respective boundary lines. Accepted as the best available evidence of the position of the original corner.
See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon Co. Std. Mon stamped K-8 17614
N85°W Nail & tag in 6" Poplar 32.30
N25°E Nail & tag in 14" Maple 98.55
N65°E Nail & tag in fence post 69.10
S45°W nail & tag in 6" Square fence post 5.38
Carsonite post North 1.14



Signed by *Larry L. Cavanagh* Date 12-15-93
Surveyor's Michigan License No. 17614