

8945

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

DEC 16 9 19 AM '93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>2W</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Robert J. Cavanagh
REGISTERED

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

W/post placed by Wm A. Burt 1850
Beech 14" S63°E 27
Beech 12" N42°W 49

1990 land corner recordation L-1,P-282
½"x18" capped steel bar, L. Cavanagh
N24°E 12" Maple 17.55
N73°W 3" Poplar 11.15
S21°W 3" Poplar 16.95
S52°E 4" Poplar 9.95
Fence line 20' East

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" capped iron
NE & SE witnesses also found (1990)
New fence constructed N-S direction 4' West of this corner.
Accepted as the best available evidence of the position of the original corner.

See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon Co. Std. Mon stamped K-9 17614
N24°E Nail & tag in 12" Maple 18.0
N35°W Nail & tag in 4"x4" Fence post 7.65
S17°W Nail & tag in 4"x4" Fence post 12.60
S52°E Nail & tag in 4" Poplar 10.04
Carsonite post North 1.20



Signed by *Larry L. Cavanagh* Date 12-15-93
Surveyor's Michigan License No. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

Date December 7, 1993 Peer Group Approved