

8946

FEB 18 1994

ROSCOMMON COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Dec 16 9 20 AM '93
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Roscommon (County)	Located In:	Corner Code #
1. Public Land Survey	T 21N R 2W	L-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Robert L. Cavanagh
REGISTER

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 12-7-93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

W/post placed by Wm A. Burt 1850
Beech 8" N40°W 7
Hemlock 6" S70°E 34

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found.

Corner re-established Mid-way and on line between K-7 & M-7 and accepted as a careful establishment of the position of the corner.

See filed dossier for detail of report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon Co. Std. Mon stamped C-7 17614
S18°W Nail & tag in 5" Maple 19.24
S50°E Nail & tag in 12" Maple 32.16
N30°E Nail & tag in 10" Maple 23.94
N22°W Nail & tag in 9" Maple 14.90
Carsonite post North 1.23
Fence Corner is 6' West & 7.5' South



Signed by

Larry L. Cavanagh

Date

12-15-93

Surveyor's Michigan License No.

17614

Date December 7, 1993

Peer Group Approved

LIBER 3

PAGE 12