

# SURVEY & REMONUMENTATION

7APB 8 4 1995

## ROSCOMMON COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
SEP 2 8 27 AM '95

For corners in **COMMISSION**

ROSCOMMON  
(County)

Located In:

Corner Code ##

- |                                       |                          |             |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey                 | T <u>21N</u> R <u>2W</u> | <u>M-11</u> |
|                                       | T _____ R _____          | _____       |
|                                       | T _____ R _____          | _____       |
|                                       | T _____ R _____          | _____       |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____       |
|                                       | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____       |
|                                       | S _____ T _____ R _____  | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                          |             |
| 5. Private Claims _____               |                          |             |

TO BE FILED IN LIBER 3 of LAND CORNERS  
Register of Deeds Stamp & File Number

Timothy L. Lapham in a field survey on June, 1994  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11: 1837, BRINK, POST, CEDAR 10" S41W 42LKS, CEDAR 7" N6 1/2W 12LKS;  
1990, CAVANAGH, SURVEY 572-549 TO 554, COR MAT, 4 WITS;  
5/5/1990, CAVANAGH, SURVEY 572-557, COR MAT, 4 WITS,  
6/5/1990, CAVANAGH, LCRC 1-281, COR MAT 4 WITS;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11: FOUND 1/2" X 18" CAPPED STEEL BAR, EXCAVATED TO 3 FEET AND FOUND NO FURTHER EVIDENCE;  
FOUND ACCESSORIES  
N50E 45.82' SPIKE IN P. POLE  
S59E 62.6' SPIKE IN P. POLE  
WEST 21.5' S. BASE SIGN POST  
ACCEPTED FOUND CORNER AS BEST AVAILABLE EVIDENCE OF THE LOCATION OF THE ORIGINAL CORNER.  
THIS CORNER ESTABLISHED IN ACCORDENCE WITH THE ROSCOMMON REMONUMENTATION PROGRAM. SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11: SET A 2 1/2" x 24" CAST IRON MONUMENT 4" BELOW SURFACE OF ASPHALT IN A MONUMENT BOX WITH BRASS DISK MARKED "ROSCOMMON COUNTY, 1994 27595"  
N50E 45.82' SPIKE & TAG IN P. POLE  
S59E 62.6' SPIKE & TAG IN P. POLE  
WEST 21.5' S. BASE SIGN POST  
N72E 95.67' SPIKE & TAG IN P. POLE  
S22E 100.91' SPIKE & TAG IN 5" SPRUCE  
CORNER FALLS IN EXISTING ROAD CENTERLINE

*M. Lapham*  
**ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE 7-29-94**



Signed by *[Signature]*

Date 9/26/94

Surveyor's Michigan License No. 27595