

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 21 10 51 AM '93

9071

FEB 18 1994

COMMISSION

For corners in

ROSCOMMON (County)	Located In:	Corner Code -#
1. Public Land Survey	T <u>22N</u> R <u>1W</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Robert L. Lapham
REGISTER

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE 11/30/93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, TIMOTHY L. LAPHAM, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5: 1837, J.BRINK, POST, HEMLOCK 10" S57.5W 14LKS, HEMLOCK N46W 13LKS; 1852, W.BURT, POST, HEMLOCK 14" S82E 25LKS, HEMLOCK 12" N26E 33LKS; 6/27/1946, HENNING, SURVEY-SEE DOSSIER, CORNER MATERIAL, NO WITNESSES; DATE UNKNOWN, SURVEYOR UNKNOWN, LCRC 2-191, COR MAT, NO WITS; 6/11/1993, CALDWELL, CORNER RECORD CARD-SEE DOSSIER, NO COR MAT, NO WITS; 6/2/1971, L.CAVANAGH, (132) 253-607, NO COR MAT, NO WITS; 6/1971, L.CAVANAGH, LCRC 1-13, COR MAT, NO WITS; 3/23/1972, PORTER, NO COR MAT, NO WITS; 7/7/1977, L.CAVANAGH, (132) 335-227, COR MAT, 3 WITS; 3/20/1982, ROBISON, (132) 412-305, COR MAT, 3 WITS; 4/3/1987, ARLETH, (132) 504-186, COR MAT, 2 WITS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5: FOUND 19" SQUARE HEAD BOLT IN MONUMENT BOX WITH NAIL ON NORTH SIDE OF BOLT. N37W 91.25' USC&GS BM N22E 75.7' (FACE) HIGHWAY MARKER S24W 107.58' NE CORNER OF SERVICE STATION N35W 83.10' CONCRETE CORNER POST ACCEPTED FOUND CORNER AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER. THIS CORNER ESTABLISHED IN ROSCOMMON COUNTY REMONUMENTATION PROGRAM. SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5: SET 2" X 21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE IN MONUMENT BOX AZ 321° 91.25' USC&GS BM AZ 22° 75.60' FACE OF HIGHWAY MARKER AZ 201° 107.00' CORNER OF BRICK ON SERVICE STATION AZ 335° 83.00' SE CORNER OF CONCRETE CORNER POST



Signed by *Timothy L. Lapham*

Date 12/20/93

Surveyor's Michigan License No. 27595

Date 11/30/93 Peer Group Approved
LIBER 3 PAGE 35