

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

4726

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in <u>Roscommon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 1W	A - 9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

11 JUL 96 11:28 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

**TO BE FILED IN LIBER 3 OF LAND CORNER
Register of Deeds Stamp & File Number**

I, Marvin E. Myers, in a field survey on June 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	10	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Nov. 1838 J. Brinks Mon. - Post WIT: - 10" Aspen S30°W 50 lks. 16" Y.Pine N 32°W 73 lks.	Liber 2, page 203 Mon. - 5/8" Iron WIT: - 10" B.Oak N76½°E 44.3' 8" W.Oak S49°E 50.6'	Liber 628, page 383 Nov. 11, 1992 F.J. Arleth Mon. - RR Spike WIT: - 14" B.Oak S35°W 64.2' 12" B.Oak N42°W 56.6' Conc. Mon. S30°E 68.4'
Old Field Notes (Date Unknown) (Possible Delamater) Mon. - No Corner Found Set 5/8" bar in intersection WIT: - Old BT 10" B.Oak N76°E 44.3' Old BT 8" W.Oak S49°E 50.6'	Liber 332, page 150 May 1977 Henning Mon. - RR Spike WIT: - 14" B.Oak S35°W 64.2' 12" B.Oak N42°W 56.6' Conc. Mon. S30°E 68.4'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR Spike in centerline road N-S and Trail Road East
Found concrete monument S23°E 68.40'
Accepted RR Spike as the best available evidence of the position of the original corner
Replaced RR Spike with standard Roscommon County Monument

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE June 17, 1996
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Set Standard Roscommon County Monument in pavement box
WIT: Set nail SE side 14" W.Oak S50°W 59.00'
Set nail S. side 14" B.Oak N84°W 43.66'
Set nail NE side 8" J.Pine N22½°W 69.03'
Set nail NW side 4" B.Oak N81°E 71.78'



Signed by *Marvin E. Myers* Date July 1, 1996
Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1985

LIBER 3 PAGE 299