

8761

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Roscommon (County)

Corner Code #

Table with 5 rows and 4 columns: Survey Type, T, R, Corner Code. Row 1: Public Land Survey, T, 22N, R, 2W, M-11. Row 2: Property Controlling in Section, S, T, R, A-11.

STATE OF MICHIGAN ROSCOMMON COUNTY RECORDED 27 SEP 1999 9:16:35 AM ROBERT W. SMITH REGISTER OF DEEDS

TO BE FILED IN LIBER 3 OF LAND CORNERS Register of Deeds Stamp & File Number

4. Lot No: Recorded Plat: 5. Private Claims:

I, Carl T. Kiiskila, in a field survey on September 9, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

GLO- May 1838 John Brink D.S. set quarter section post Wit: 16" Yellow Pine S71°W 12 Links 8" White Oak N31°W 27 Links

G. Henning Liber 269, Page 482, November 27, 1972, shows corner. No monument description or witnesses were recorded.

Roscommon County Dept. of Engineering Jan. 27, 1965, engineer N. Sageman found a 1 1/4" pipe for corner, per 1948 road plans.

G. Henning RLS Liber 333, Page 311, July 12, 1977, shows corner. Wit: 9" B. Oak N38°E 88.0' 10" B. Oak N83°E 79.7'

G. Henning RLS# 2240, section 25 sketch, no date shows corner position. No monument description or witnesses were recorded.

Larry Cavanagh RLS #17614 Liber 361, Page 459, March 20, 1979, found 1"X24" pipe in corner. Wit: 9" B. Oak N38°E 88.0' 10" B. Oak N83°E 79.7'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

Found 1 5/8" automotive valve in the centerline of North-South Road. Accepted 1 5/8" automotive valve as the best available evidence of the original corner position. Replaced 1 5/8" automotive valve with standard Roscommon County Monument.

ROSCOMMON COUNTY PEER GROUP APPROVAL DATE Sept 10, 1999

Marvin E. Myers, P.S. County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Roscommon County Monument in pavement box. Wit: Set nail in 12" Oak N45°E 87.92' Set nail in Utility Pole S36°E 39.06' Set nail in Utility Pole S51°W 39.48' Center of Crimson Maple N42°W 77.72'



Signed by: Carl T. Kiiskila Surveyor's Michigan License No.: 33981

Date: 9-16-99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 28, 1971 Revised May 14, 1975 Revised Jan. 1983 Revised Oct. 1995



LIBER 3 PAGE 606

SURVEY & RECORDATION

MAR 1 2000

SECTION