

ROSCOMMON COUNTY REMONUMENTATION

9069

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Dec 21 10 51 AM '93

For corners in

ROSCOMMON
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 22N R 1W B-5
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 11/30/93

TO BE FILED IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, TIMOTHY L. LAPHAM, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5: 1852, W.BURT, POST, BEECH 6" N22W 16LKS, BEECH 6" S75E 20LKS;
DATE UNKNOWN, SURVEYOR UNKNOWN, LCRC 2-150, CORNER MATERIAL, 4 WITNESSES;
6/11/1963, CALDWELL, CORNER RECORD CARD-SEE DOSSIER, COR MAT, 4 WITS;
6/1971, L.CAVANAGH, LCRC 1-13, COR MAT, 3 WITS;
3/22/1976, L.CAVANAGH, (132) 316-296, NO COR MAT, NO WITS;
5/25/1977, HIGGINS, (132) 332-595, NO COR MAT, NO WITS;
5/4/1979, ARLETH, (132) 373-676, COR MAT, 2 WITS;
3/30/1982, ROBISON, (132) 412-305, COR MAT, 3 WITS;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5: FOUND 3/4" PIPE IN MONUMENT BOX IN CENTER LINE ROAD E-W
N25W 65.88' 6" N. PINE
NORTH 75.43' FENCE CORNER (E-W-N)
N30W 49.19' TELEPHONE POLE
S20W 72.55' TELEPHONE POLE
N05W 48.75' 18" BASSWOOD
ACCEPTED FOUND CORNER AS BEST EVIDENCE OF POSITION OF ORIGINAL CORNER.
THIS CORNER ESTABLISHED IN ROSCOMMON COUNTY REMONUMENTATION PROGRAM.
SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5: SET 2" X 21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE IN MONUMENT BOX
AZ 335° 65.98' MSHD TAG IN SW FACE 7" RED PINE
AZ 327° 49.00' SPIKE WITH TAG #9433 NE FACE TELEPHONE POLE
AZ 204° 72.44' SPIKE WITH TAG #9433 NW FACE POLE
AZ 355° 48.87' SPIKE IN WEST FACE 18" BASSWOOD



Signed by [Signature]

Date 12/20/93

Surveyor's Michigan License No. 27555

Date 11/30/93 Peer Group Approved

LIBER 3 PAGE 33