

FEB 16 1994
9065
COMMISSION

ROSCOMMON COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Dec 21 10 51 AM '93

For corners in

<u>ROSCOMMON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>1W</u>	<u>B-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Robert L. Lapham
REGISTERED PROFESSIONAL SURVEYOR

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE 11-30-93

TO BE FILED IN LIBER 3 OF LAND CORNERS

Register of Deeds Stamp & File Number

I, TIMOTHY L. LAPHAM, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-6: CORNER NOT SET IN GLO SURVEY OR ANY SUBSEQUENT SURVEY OF RECORD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-6: SET CORNER AT MATHEMATICAL INTERSECTION OF STRAIGHT LINES CONNECTING NORTH WITH SOUTH 1/4 CORNERS WITH EAST WITH WEST 1/4 CORNERS.
THIS CORNER ESTABLISHED IN ROSCOMMON COUNTY REMONUMENTATION PROGRAM.
SEE DOSSIER FOR DETAILED REPORT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-6: SET 2" X 21" CAST IRON MONUMENT WITH BRASS ROSCOMMON COUNTY PLATE
AZ 06° 8.02' SPIKE AND TAG WEST FACE 10" POPLAR
AZ 281° 24.60' SPIKE AND TAG SOUTH FACE 9" POPLAR
AZ 180° 61.35' SPIKE AND TAG EAST FACE 6" OAK
AZ 116° 101.77' SPIKE AND TAG NORTH FACE 14" MAPLE
AZ 0° 1.0' CARSONITE SURVEY MARKER POST



Signed by *Timothy L. Lapham* Date 12/20/93
Surveyor's Michigan License No. 27895

Date 11/30/93 Peer Group Approved

LIBER 3 PAGE 29