

SURVEY & REMONUMENTATION

APR 07 1998

9235

SECTION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN  
ROSCOMMON COUNTY  
RECORDED

16 DEC 97 12:22 P.M.

ROBERT W. SMITH  
REGISTER OF DEEDS

For corners in  
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N R 1W D-13  
T22N R 1W D-1  
T R  
T R

I, Larry L. Cavanagh, in a field survey November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNERS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838  
SET POST BALSAM 8" N66 1/2E 13 LKS  
BALSAM 8" N66 1/2E 13 LKS  
BALSAM 7" N14W 13 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE FOUND  
FENCE CORNER WEST 60±, NORTH 52±, FENCE RUNNING SOUTH & EAST, NOT USED AS EVIDENCE FOR CORNER LOCATION.  
SET AT SINGLE PROPORTIONATE DISTANCE BETWEEN C-13 (N88°47'46"W 2638.90') AND E-13 (S88°47'46"E 2638.90')


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614 1997  
NAIL & TAG IN 12" MAPLE SOUTH 18.40'  
NAIL & TAG IN 7" MAPLE EAST 21.63'  
NAIL & TAG IN 10" MAPLE S75°W 56.46'  
NAIL & TAG IN 10" MAPLE N35°W 68.55'  
CARSONITE POST NORTH 1.3'

A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

ROSCOMMON COUNTY  
PEER GROUP APPROVAL  
DATE Dec 5, 1997

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh* Date Dec 11, 1997  
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER 3 PAGE 460