

**SURVEY &
REMONUMENTATION**

APR 07 1998

SECTION

9234

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 12:21 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R 1W	E-13
T22N	R 1W	E-1
T	R	
T	R	

I, Larry L. Cavanagh, in a field survey November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838 SET POST WHITE PINE 6" N68E 32 LKS BIRCH 4" N18W 24 LKS	1970'S L2 P147 1/2" BAR N35°E 38.71' 15" J. PINE S40°W 37.44' FE COR POST N22°W 64.45' 10" MAPLE N53°W 91.92' 15" MAPLE
WILLIAM BURT 1852 WHITE PINE 24" SOUTH 63 LKS MAPLE 5" S79E 19 LKS	
N.C. CALDWELL 12018, 1966 WIT: FD 1/2" BAR AT CENTERLINE OF ROADS EAST AND SOUTH N35°E 38.71' 15" J. PINE S40°W 37.44' FE COR POST N22°W 64.45' 10" MAPLE N53°W 91.92' 15" MAPLE	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" X 2' BAR
S40°W FENCE CORNER POST 37.44'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614 1997
NAIL & TAG IN 5" R. OAK N33°E 133.85'
NAIL & TAG IN POWER POLE S58°E 53.48'
NAIL & TAG IN FENCE POST S40°W 37.75'
NAIL & TAG IN 6" MAPLE N52°W 91.22'
DNR POST N4°W 19.85'
CARSONITE POST NORTH 19.8'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE DEC 5, 1997**

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh*
Surveyor's Michigan License NO. 17614

Date Dec. 11, 1997

LIBER 3 PAGE 459