

**SURVEY &
REMONUMENTATION**

APR 07 1998

9231 SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N	R1W	H-13
T22N	R1W	H-1
T	R	
T	R	

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 12:20 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838
SET POST
WHITE PINE 10" N72 1/2E 38 LKS
BLACK OAK 14" N35W 16 LKS

1970'S L2 P147
1/2" BAR
SO. 33' 1/2" BAR
N35°W 66.0' 6" MAPLE
N38°E 46.21' 8" MAPLE
S18°W 58.0' 5" MAPLE

	A	B	C	D	E	F	G	H	I	J	K	L	U
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PAVEMENT BOX, NO MONUMENT
1/2" BAR SOUTH 33.0'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614, 1997
NAIL & TAG IN 15" R. OAK S40°W 119.48'
NAIL & TAG IN 12" R. OAK S39°E 87.81'
1/2" BAR SOUTH 33.06'
NAIL & TAG IN 6" MAPLE N22°E 45.92'
NAIL & TAG IN 3" MAPLE N35°W 65.29' (GROWING OUT OF A STUMP, POSSIBLE OLD WITNESS)
CARSONITE POST NORTH 28.9'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 5, 1997**

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh* Date *Dec. 11, 1997*
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 456