

SURVEY & REMONUMENTATION

APR 07 1998

9229

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 12:20 P.M.

ROBERT W. SMITH
REGISTER OF DEEDS

For corners in
Roscommon County

Located in: Corner Code #

1. Public Land Survey

T23N R 1W K-13
T22N R 1W K-1
T R
T R

I, Larry L. Cavanagh, in a field survey November, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

JOHN BRINK 1838
SET POST
PITCH PINE 12" N84E 68LKS
PITCH PINE 12" N21 1/2W 55 LKS

WILLIAM BURT 1852
W. PINE 24" S86E 41 LKS
W. PINE 8" S80W 24 LKS

GEORGE HENNING 1944
SURVEY REPORT
CALL FOR FINDING ORIG. CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" X 2' PINCH PIPE WITH POINT OF PINE POST
(I-13 TO K-13, HENNING 5297.1', MEASURED 5292.74')
(K-13 TO M-13, HENNING 5359.86', MEASURED 5354.43')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ROSCOMMON COUNTY MONUMENT STAMPED 17614, 1997
NAIL & TAG IN 24" BLAZED PINE STUMP (MARKED B.T.) SOUTH 20.37'
NAIL & TAG IN 21' W OAK N25°W 44.83'
NAIL & TAG IN 4" W. PINE DUE EAST 14.53'
CARSONITE POST S65°W 1.05'

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE Dec 5, 1997

Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh Date Dec. 14, 1997
Surveyor's Michigan License NO. 17614

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 4454